17	Digging of trench of 0.6m deep x 0.5m wide refilling the trench to the required level and consolidating etc., Complete as per specifications.	Mtrs	75.00	50.00	Rupees Fifty Only
18	Supplying and fixing of porcelain fuse channel with cut-out on existing / new wooden panel using neccesary nuts, bolts and washers etc., Complete as per specifications.	Nos	50.00	219.00	Rupees Two Hundred Nineteen Only
19	Earthwork excavation for foundation of buildings water supply, sanitary lines and electrical conduits either in pits or in trenches 1.5m and above in width, in hard soil not exceeding 1.5 m. in depth including dressing the bottom and sides of pits and trenches, stacking the excavated soil clear from edges of excavation with lead upto 50 m. after breaking of clods Complete as per specifications.	Cum	308.25	219.00	Rupees Two Hundred Nineteen Only
20	Providing and installing at site of work P.V.C pipees including cost of pipes and specials and labour including lowering into trenches, laying true to line, level and perfect linking at joints leak proof including jointing of approved type with all labour and lift charges, handling charges including encasing the pipe alround to a depth not leass than 15 cms with gravel or selected earth available from the excavation etc., Complete as per specifications.	Rmt	685.00	157.00	Rupees One Hundred Fifty Seven Only
21	Refilling available earth around pipe lines, cables in layers not exceeding 20cms in depth, compacting each deposited layer by ramming after watering with lead upto 50m. and lift upto 1.5m. Including cost of all labour Complete as per specifications.	Cum	308.25	51.41	Rupees Fifty One and Forty One Paise Only
22	Transportation of pumping machineries Complete as per specifications.	Nos	4.00	850.00	Rupees Eight Hundred Fifty Only
23	Erection of Pumping machineries Complete as per specifications.	Rmt	4.00	850.00	Rupees Eight Hundred Fifty Only

Signature of the Contractor

Technical Manager (TM-2)
KRIDL, Dasarahalli Zone, Bangalore

Executive Engineer,
Dasarahalli Division

Received by
5/5/14